

City of Rialto

Bid Results for Project Various Streets Reconstruction Phase II, 240802 (24-011)

Issued on 12/11/2023

Bid Due on January 11, 2024 3:00 PM (PST)

Item Number	Section	Description	Unit of Measure	Quantity	Calmex Engineering, Inc.	Granite Construction Company	R.J. Noble Company	All American Asphalt
1	Bid Schedule	Mobilization	LS	1	\$238,200.00	\$200,000.00	\$525,000.00	\$250,000.00
2	Bid Schedule	Water Pollution Control	LS	1	\$25,000.00	\$140,000.00	\$50,000.00	\$150,000.00
3	Bid Schedule	Traffic Control	LS	1	\$850,000.00	\$400,007.20	\$400,000.00	\$2,206,793.52
4	Bid Schedule	Construction Surveying and Monuments	LS	1	\$124,000.00	\$85,000.00	\$95,000.00	\$200,000.00
5	Bid Schedule	Railroad Coordination	LS	1	\$5,300.00	\$23,000.00	\$35,000.00	\$80,000.00
6	Bid Schedule	Construct Access Ramp	EA	72	\$835,200.00	\$345,600.00	\$482,400.00	\$936,000.00
7	Bid Schedule	Remove Existing and Construct 4" Sidewalk	SF	1864	\$29,824.00	\$39,144.00	\$31,688.00	\$33,552.00
8	Bid Schedule	Cold Mill Existing Asphalt Concrete Pavement	SF	56056	\$89,689.60	\$140,140.00	\$100,900.80	\$126,126.00
9	Bid Schedule	Unclassified Excavation	CY	7424	\$675,584.00	\$779,520.00	\$779,520.00	\$890,880.00
10	Bid Schedule	Pulverized Asphalt Base (PAB)	CY	7853	\$455,474.00	\$628,240.00	\$824,565.00	\$157,060.00
11	Bid Schedule	Pulverizing of Existing AC, AB (Depth per Plan)	SF	578831	\$636,714.10	\$463,064.80	\$868,246.50	\$46,306.48
12	Bid Schedule	Rubberized Hot Mix Asphalt Gap Graded (RHMA-G)	TON	7806	\$1,327,020.00	\$1,951,500.00	\$1,170,900.00	\$1,170,900.00
13	Bid Schedule	Hot Mix Asphalt (Type A)	TON	10600	\$1,537,000.00	\$1,961,000.00	\$1,325,000.00	\$1,484,000.00
14	Bid Schedule	Remove and Construct 6-Inch Curb	LF	102	\$10,200.00	\$9,690.00	\$9,894.00	\$25,500.00
15	Bid Schedule	Remove 8-Inch Curb	LF	102	\$3,570.00	\$2,244.00	\$2,856.00	\$3,060.00
16	Bid Schedule	Construct 8-Inch Curb and Gutter	LF	102	\$8,160.00	\$15,300.00	\$7,854.00	\$12,240.00
17	Bid Schedule	Remove and Construct 8-Inch Curb and Gutter	LF	204	\$23,868.00	\$25,500.00	\$25,500.00	\$30,600.00
18	Bid Schedule	Remove Existing and Construct Cross Gutter and Spandrel (RSC)	SF	14459	\$506,065.00	\$347,016.00	\$867,540.00	\$433,770.00
19	Bid Schedule	Adjust all Valves, Frames and Covers to Grade	EA	104	\$57,200.00	\$111,800.00	\$166,400.00	\$145,600.00
20	Bid Schedule	Adjust Manhole Frame and Covers to Grade	EA	55	\$82,500.00	\$79,750.00	\$88,000.00	\$88,000.00
21	Bid Schedule	Parkway Drain Structure	LS	1	\$23,000.00	\$40,300.00	\$40,000.00	\$34,000.00
22	Bid Schedule	Traffic Striping, Signage, and Markings	LS	1	\$115,000.00	\$70,284.00	\$75,000.00	\$70,000.00
23	Bid Schedule	Traffic Detector Loops	EA	10	\$6,800.00	\$6,500.00	\$7,500.00	\$7,000.00
24	Bid Schedule	Pedestrian Push Buttons	LS	1	\$8,800.00	\$8,400.00	\$3,800.00	\$3,500.00
25	Bid Schedule	Field Orders	LS	1	\$390,000.00	\$390,000.00	\$390,000.00	\$390,000.00
					\$8,064,168.70	\$8,263,000.00	\$8,372,564.30	\$8,974,888.00